contract: m/s. welspun Enterprises

GLOBAL GROUND WATER CONSULTANTS

m/s. Pumps Enterprises

84-III Floor, Humayunpur, Safdarjung Enclave, New Delhi - 110 029
Mobile : 9818 888 824, 9818 007 038
E-mail : srikanthchukka.c23@gamil.com, ravikanth44@yahoo.com

KUSUW

GEOPHYSICAL ELECTRICAL LOGGING REPORT AT

Tubewell No. : .....

Date : 28.03.2022

Village : HARWANPUR, Singrawati

Block : Siyana

District : Buland sahar, U.P

Depth in Metres	Expected Litholog	Expected Water Quality
0 - 3m	surface soil	
3 - 13	Sand	
13 - 22	Fine sand	good
22 - 25	sandy clay	
25 - 38	medium sand	good
38 - 42	clay	
42 - 97	medium sand	good
97 - 122	clay kankar	
122 - 126	Fine sand	good
126 - 130	Sandy clay	
130 - 150	Fine sand	good

For Global Groundwater Consultants

M. RAVI KANTH
28/3/2022

EXPECTED WATER ZONE

WATER LEVEL : 13 METRES