State Water & Sanitation Mission
NAMAMI GANGE AND RURAL WATER SUPPLY DEPARTMENT
Government of Uttar Pradesh

aarvee associates
architects engineers & consultants pvt. ltd.

Contractor: welspun
SE: Mr. Rohit

# GLOBAL GROUND WATER CONSULTANTS

84-III Floor, Humayunpur, Safdarjung Enclave, New Delhi - 110 029
Mobile : 9818 886 824, 9818 007 038
E-mail : srikanthchukka.c23@gamil.com, rawikanth44@yahoo.com

(RAW)

## GEOPHYSICAL ELECTRICAL LOGGING REPORT AT

Tubewell No. : .....

Date : 2.06.2021

Village : Alampur urf Torai Bangar

Block : Anup Sahar

District : Bulandsahar

| Depth in Metres | Expected Litholog | Expected Water Quality |
|---|---|---|
| 0 - 3m | Buke soil | |
| 3 - 7 | Fine sand | |
| 7 - 15 | Fine sand | Good |
| 15 - 20 | clay | |
| 20 - 33 | medium sand | good |
| 33 - 47 | Sandy clay kankar | |
| 47 - 93 | medium sand | good |
| 93 - 99 | Fine sand | good |
| 99 - 106 | clay | |
| 106 - 128 | medium sand | good |
| 128 - 134 | Fine sand | good |
| 134 - 150 | medium sand | good |

For Global Groundwater Consultants

M. RAVI KANTH 2/6/2021
(Hydrogeologist)

EXPECTED WATER ZONE

WATER LEVEL : .....7..... METRES

Consulting Geologists, Geophysists & Ground Water Specialists