GSTIN : 09AEOPG8965L2ZJ

GROUND WATER SURVEY CONSULTANCY
GEOLOGISTS, GEOPHYSICISTS & TUBEWELL ENGINEERS

AGRA
ESTD. 2010

112 A-Shree Nagar Colony, Firozabad Road, Agra- 282006
Mob. : 9761163000, 9794625420, Email : gwsc_agra@yahoo.com

Ref No.....................

Date..13./.02./.2024.........

GEOPHYSICAL ELECTRICAL WELL LOGGING FIELD REPORT
DETAIL OF WATER BEARING ZONNES

Name Of Agency-.........wellspoun......Krishna....Industries........................
Village -...............Nagla Nalu.......... Block-..............Anupshahar......
District-.............Bulandshahr:....... Logging Depth-...............140. mtr:......
Drilling Depth- ....140. mtr:.......... Water Level-.................11. mtr:...........

S.No	Depth in Mtr.	Lithology	Expected Water Quality
1	0 – 5	Surface Soil	
2	5 – 8	Dry Sand	
3	8 – 19	clay Konkar	
4	19 – 25	Fine Sand	
5	25 – 32	clay Konkar	
6	32 – 36	Fine Sand	med. to Good
7	36 – 50	clay Konkar	
8	50 – 66*	medium Sand	med to Good
9	66 – 73	clay Konkar	
10	73 – 85*	medium Sand	med. to Good
11	85 – 91	clay Konkar	
12	91 – 98*	Fine to med Sand	med to Good
13	98 – 100	clay Konkar	
14	100 – 102	Fine Sand	med. to Good
15	102 – 110	clay Konkar	
16	110 – 118*	medium Sand	med to Good
17	118 – 122	clay Konkar	
18	122 – 127*	Fine to med Sand	med. to Good
19	127 – 131	clay Konkar	
20	131 – 135*	Fine to med Sand	med. to Good
21	135 – 140	clay Konkar	
22			
23			

* Expected Water Bearing Zone

For Ground Water Survey Consultancy

Geophysicist

Spesializations In