E. Photograph of observations made at the site

Contractor: M/S. L.C. Infra Projects Pvt. Ltd Ahmedabad.

GLOBAL GROUND WATER CONSULTANTS

84-III Floor, Humayunpur, Safdarjung Enclave, New Delhi - 110 029
Mobile : 9818 888 824, 9818 007 038
E-mail : srikanthchukka.c23@gamil.com, ravikanth44@yahoo.com

GEOPHYSICAL ELECTRICAL LOGGING REPORT AT

Tubewell No. : .....

Date : 18.06.2022

Village : BALI

Block : BHAGPAT

District : BAAGPAT, U.P

Depth in Metres	Expected Litholog	Expected Water Quality
0 - 3m	Surface soil	
3 - 8	clay kankar	
8 - 18	Fine sand	
18 - 31	medium sand	good
31 - 36	clay	
36 - 71	medium sand	good
71 - 82	clay	
82 - 94	Sandy clay kankar	
94 - 110	medium sand	good
110 - 127	clay	
127 - 133	Sandy clay kankar	
133 - 136	Fine sand	good

For Global Groundwater Consultants

M. RAVIKANTH
18/6/2022

EXPECTED WATER ZONE

WATER LEVEL : 17 METRES

Consulting Geologists, Geophysists & Ground Water Specialists

Fig No:-05-Logging Report