# GROUND WATER SURVEY CONSULTANCY

GEOLOGISTS, GEOPHYSICISTS & TUBEWELL ENGINEERS

### GEO-PHYSICAL WELL ELECTOLOGGING REPORT

Ref No:-N-1288

Date: - 23-02-2023

NAME OF SITE

GRAM PANCHAYAT-Bodpur

Commence of the Party of the Pa

BLOCK-Shahbad

DISTT-Rampur

NAME OF AGENCY

NKG Infrastructure Limited New Delhi



#### GROUND WATER SURVEY CONSULTANCY

Electric Well Logging, Geophysical Resistivity Survey, Ground Water Investigations. 112 A-Shree Nagar Colony, Firozabad Road, Agra- 282006 (M): 9412260823, 9794625420, 9761163000, Email: gwsc\_agra@yahoo.com

ISO; 9001: 2015

Ground Water Survey Consultancy

## REPORT ON GEOPHYSICAL WELL LOGGING

GRAM PANCHAYAT- BODPUR, BLOCK- SHAHBAD, DISTT- RAMPUR
UNDER
JAL JIVAN MISSION


#### Introduction:

A Deep bore hole was drilled 140 mtrs. depth and logged depth 140 mtrs. at above site was drilled by NKG Infrastructure Limited, New Delhi.

On the request of NKG Infrastructure Limited, New Delhi. a Geophysical well Logging is conduct at above bore hole using IGIS Well Logger on 23.Feb.2023.

Logging Para meters - Self potential, short normal (N-16), Long Normal (N-64), Lateral. Details of major aquifer formations explored from logging of bore hole combined with the study of Strata Chart prepared from drill cuttings are given in the following table:-

CNIO	Defth range(m)	Thickness(m)	Lithology	Expected
S.No.	Deltin range (iii)			Water Quality
1	0 - 5	5	Surface soil	
2	5 - 10	5	Clay kankar	
2.	10 - 23	13	Fine to Medium sand	Medium
1	23 - 26	3	Clay kankar	
4.	26 - 51	25	Medium sand	Medium
).	51 - 55	4	Clay kankar	
7	55 - 82*	27	Medium sand	Medium
0	82 - 91	9	Clay kankar	
8.	91 - 95*	4	Fine to Medium sand	Medium
9.		5	Clay kankar	
10.	95 - 100	18	Medium sand	Medium
11.	100 - 118*	10	Clay kankar	
12.	118 - 130	12		Medium
13.	130 - 140*	10	Medium sand	Ivicuitii



### conclusions and Recommendations :-

- 1. The Lithology broadly tallies with that of drill cutting strata chart.
- The zones marked with asterisk (\*) appear to be aquifer zones for possible Development of tubewell.
- 3. The Quality of water is expected Medium.
- 4. It is recommended to have a chemical and bacteriological analysis of the water sample before using it for human consumption or for any other use.
- 5. All projections and recommendations are subject to the inherent limitations of the technique employed and there could be variations as the underground conditions are not always amenable to physical interpretations.

Ground Water Survey Consultancy



