# GEO-PHYSICAL WELL ELECTROLOGGING REPORT

Re No -08/229

Date-23/08/2023

NAME OF SITE

BINDOUR KHAJUHA FATEHPUR

NAME OF AGENCY

M/S PMPL-BRCCPL (JV) FATEHPUR

## M/S MAHALAXMI TUBE WELL

CONSTRUCTION OF DEEP AND SHALLOW TUBEWELL, WELL ELECTRO-LOGGING AND DEVELOPMENT OF TUBE WELL BY AIR COMPRESSUR RAJENDRA NAGAR MILL COLONY PUKHRAYAN KANPUR, 209111 9935299290, 8090118811, mahalaxmitubewell@gmail.com

ISO: 9001:2015

# M/s Mahalaxmi Tube well



Rajnendra Nagar Pukhrayan Kanpur 9935299290 mahalaxmitubewell@gmail.com

## **Geophysical Well Logging Report**

Ref No – 08/229 Date – 23/08/2023

Site Location : - Bindour Khajuha Fatehpur

District : - Fatehpur

Logged Depth : - 139 M BGL

Date of Logging : - 22/08/2023

Types of Log : - S.P& N16, N-64 LAT

Logger used : - IGIS

Name of Agency : - M/S PMPL-BRCCPL (JV) Fatehpur

Rm -16.7  $\Omega$ m Rw -16.6  $\Omega$ m


The following permeable granular zones have been deciphered with the

#### help of Electrical Logger

Sr N0	Depth Range From M.B.G.L	Depth Range M.B.G.L.	Thickness Mtr.	Inferred Lithology	Quality of G.W.
01	35	38	03	11	
02	50	53	03		
03	56	63	07		A II . O I
04	86	92	06	Fine to medium Sand	All Good
05	96	99	03	100	
06	107	113	06		

Note- All zones are intermixed with fine bands of kankar.

M/s Mahalaxmi Tube Well





# **Jal Jeevan Mission**





### District Level Water Analysis Laboratory , U.P Jal Nigam, (Rural) Fatehpur

Construction division, U.P Jal Nigam, Sadipur, Fatehpur (Test Address only )

### **Test report**

Sample ID:

U719011S16398256

### **User Information**

Name:	Syed Mohd shabaz	Mobile:	9473942669			
Email:	ee2cdupjn.alld@gmail.com	Pin Code:				
Full Address:	Village- Not available , Gram Panchayat- Not available, Block- Not available, District- Prayagraj, State- Uttar Pradesh					
Sample description						
Source of	Others, location : Bindour WSS TW02	Village:	Bindour			
Sample:  Gram Panchayat:	Bindour	Block:	Khajuha			
District:	Fatehpur	State:	Uttar Pradesh			
Address:		Remarks:	Gram- Bindour WSS TW02 Block- Khajhua Dist- Fatehpur			
Latitude:		Longitude:				
Date & time of sample collection						
20.09.2023   02:55:00 PM						
Date & time of sample received in lab						
27.11.2023   05:30:00 PM						
Date & time of sample analysed  28.11.2023   03:10:00 PM						
Date & time of report generation  03.12.2023   01:32:02 AM						

### Test results

Sr. No.	Parameters tested	Unit of measurement	Requirement (acceptable limit) as per BIS 10500	Permissible limit (in absence of alternate source) as per BIS 10500	Test result value	Remarks
1	Chloride (as Cl)*	mg/I	250	1000	58.000	
2	Colour	Hazen units	5	15	0.000	NT
3	Fluoride (as F)*	mg/I	1	1.5	1.020	
4	Iron (As Fe)*	mg/I	1	No Relaxation	0.160	
5	Nitrate (as NO3)*	mg/I	45	No Relaxation	12.000	
6	рН*	NA	6.5-8.5	No Relaxation	7.360	
7	Sulphate (as SO4)*	mg/I	200	400	42.000	
8	TDS	mg/I	500	2000	472.000	
9	Total Alkalinity (as Calcium Carbonate)*	mg/I	200	600	248.000	
10	Total Arsenic (As As)*	mg/I	0.01	No Relaxation	0.000	NT
11	Total coliform*	CFU/ 100 ml	Shall not be detectable in any 100 ml sample	No Relaxation	0.000	
12	Total Hardness (As CaCO3)*	mg/I	200	600	216.000	
13	Turbidity*	NTU	1	5	1.360	

#### Note:

- 1)\*indicates parameters that are NABL accredited.
- 2)This test results related to the sample tested above
- 3)The report shall not to be reproduced in full without approval of authority
- 4)This is the end of the report

Authorised signatory
Ranvijay Singh (Test Lab Incharge)

#### Jal Jeevan Mission aims at potable tap water supply to every home

Let's join hands to ensure drinking water is potable. It helps in preventing water borne diseases and improve public health.

Designed & Developed by NIC. Copyright @copy NJJM 2023

Print

implemention of various rural water supply project including O&M for 10 Year for Bindour 2nd village, Block-Khajuha, District-Fatehpur of the State of Uttar Pradesh Under Jal Jeevan Mission

Phase-III Project Name :

Actual Lowering Chart at Vill. Bindour 2nd 300\*200

Discharge = 775 LPM

Block 1 District 1 Bindour 2nd Khajuha Fatehpur

Sr No.		
1	TW Const. By	M/s PMPL- BRCCPL(JV)
2	Size of Borewell	300°200
3	Date of Logging	23-08-23
4	Date of Lowering	26-08-23

Abstract of Pipe					
Sr. No.	Discription	иом	ltem	Qty	
1	300MM	MTR	PLAIN PIPE	60.00	
2	300MM	MTR	SLOTTED PIPE	6.00	
3	300°200	MTR	Reducer	0.20	
4	200 MM	MTR	PLAIN PIPE	38.34	
5	200 MM	MTR	SLOTTED PIPE	15.00	
-					
			Total Length	119.54	

Logging Report					
Sr. No.	Discription	Thickess(M)	Quality of G.W		
1	35-38	3			
Ž	50-53	3			
3	56-63	7	* 4		
4	86-92	6	ALL GOOD		
5	96-99	3			
6	107-113	6	•		

Note: 1- All zones Intermixed with thin bands of kankar.

